

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Gladwin Located In _____ Corner Code # _____
(County)

- | | | | | | |
|--------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>20N</u> | R | <u>2E</u> | <u>G11</u> |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 26, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- G11 – GLO – J. Mullett – 1846
Hemlock 14" S46°E 28 L.
Hemlock 10" N38°W 27 L.
- CCC –1930's - N. 78.44 - Sec. post 5 L. E. of random
Y. Pine 10" N59½°W 75
W. B. 10" S67°W 1.05

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G11 – Sec. Corner common to Sec. 27, 28, 33 & 34 – Found 1 ¾" iron pipe stub in concrete block in 'T' gravel road intersection – 1.0' below surface of road. Common Schaaf Monument set by CCC. Mon. is 1' E. of centerline gravel road N. and 1' S. of centerline E-W gravel rd. CCC Notes indicated they found original post here. One CCC Witness in place. 1 ¾" pipe stub in conc. block accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G11 – Lowered conc. block mon. and raised with 4" DOC (DNR) brass cap on 1" x 38" pipe w/ Tin can w/ concrete around cap - down 0.5'.
N59°W 49.90' to set N & T in NE side 20" R. Pine (CCC)
S45°W 41.41' to set N & T in NW side 18" R. Maple
S53°E 29.00' to set N & T in SW side 10" R. Maple
N37°E 48.41' to set N & T in SE side 6" R. Maple
Set Blue Carsonite Post with loc. tag 33' S.



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 5/9/2007