

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Gladwin Located In _____ Corner Code # _____
(County)

- | | | | | | |
|--------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>20N</u> | R | <u>2E</u> | <u>G13</u> |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

Register of Deeds Stamp & File Number _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on March 3, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G13 – GLO – Set Post – L. Clason – 1837
 S. Maple 7" N27°W 7 L.
 Tam. 7" N60°E 3 L.
 (Closing Corner is 48 L. West)
 - CCC Notes – 1930's – West 240 CH –
 Set Random post. Random post is 1.51 S & 59 W of post ('G1' or 'G13?')

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G13 – Standard Corner common to Sec. 33 & 34, T20N, R2E – Fd. 1 1/2" iron pipe in grassy marsh that is consistent with CCC monumentation along the township line. Also found 1 1/2" iron pipe for 'G1' T19N, R2E is 31.55' West (31.68' – GLO). No evidence of GLO BT's. Measured North 1221' (GLO & M) to edge of marsh. 1 1/2" iron pipe accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G13 – Drove 4" DNR Alum. Cap on 1" x 5' long galv. iron pipe into found 1 1/2" iron pipe
 S8°W 33.95' to set 1/2" x 30" rebar
 S88°E 27.81' to set 5/8" x 22" rebar
 N47°W 37.98' to set 1/2" x 30" rebar
 West 31.55' to 'G1', T19N, R2E – DNR Mon. in fd. 1 1/2" iron pipe.
 Set Blue Carsonite Post 1' West



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007