

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Gladwin Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

- |                                      |   |            |   |           |           |
|--------------------------------------|---|------------|---|-----------|-----------|
| 1. Public Land Survey                | T | <u>20N</u> | R | <u>2E</u> | <u>H9</u> |
|                                      | T | _____      | R | _____     | _____     |
| 2. Property Controlling in Section   | S | _____      | T | _____     | _____     |
|                                      | S | _____      | T | _____     | _____     |
| 3. Miscellaneous Property in Section | S | _____      | T | _____     | _____     |
|                                      | S | _____      | T | _____     | _____     |

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Feb. 7, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9								●					
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

H9 – GLO – Set ¼ post – J. Mullett – 1846  
 W. Pine 12" N53°W 19 L.  
 Hemlock 6" S69°E 19 L.  
 - CCC Notes – 1930's – West  
 between 22 & 27 – 200:00 - Set Random ¼ Post

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H9 – ¼ Corner common to Sec. 22 & 27 – No GLO evidence found. Set 4" DNR Alum. Cap on 1" x 5' long galv. iron pipe by single proportion between 'G9' and 'I-9'. Monument fall at S. Edge of Tag Elder, B. Ash Swamp. DNR Mon. accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H9 – 4" DNR Alum. Cap on 1" x 5' long galv. iron pipe  
 Set Blue Carsonite Post 1' N  
 N48°E 16.43' to set N & T in N. side 6" Elm scribed 'XBT'  
 N34°W 20.56' to set N & T in SW side 5" Ash scribed 'XBT'  
 S57°W 88.58' to set N & T in SE side 16" R. Maple scribed 'XBT'  
 S17°E 51.54' to set ¾" x 1.1' long iron pipe



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007