

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Gladwin _____
 (County)

1. Public Land Survey T 20N R 2E I-8
 T _____ R _____

2. Property Controlling
 in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous
 Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22	●	23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Craig W. McVean, in a field survey on Feb. 22, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-8 – GLO – Set ¼ Post – J. Mullett – 1846
 - B. Ash 12" N24°W 35 L.
 - B. Ash 12" S16°E 38 L.
 - CCC Notes – 1930's – North between Sec. 22 & 23 - 200.00 – Set Random ¼ post

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-8 – ¼ Corner common to Sections 22 & 23 - No GLO evidence found. Set 1" X 5' long galvanized iron pipe with 4" Aluminum DNR cap by single proportion to GLO between reestablished 'I-9' and found 'I-7'. Corner falls in Black Ash Swamp. DNR Mon. accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-8 – 4" DNR Alum. Cap on 1" x 5' long galv. iron pipe.
 - Set Blue Carsonite Post 1' North.
 - N51°W 31.24' to set N & T in SW side 13" Ash scribed 'XBT'
 - N41°E 9.42' to set N & T in SE side 3" Red Maple
 - S62°E 30.73' to set N & T in NE side 6" White Birch
 - S38°W 82.19' to set N & T in SE side 8" Cedar



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007