

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____
 Gladwin Co. _____ Located In _____ Corner Code # _____
 (County)

1. Public Land Survey		T	20N	R	2E	I-9	
		T		R			
2. Property Controlling in Section		S		T		R	
		S		T		R	
3. Miscellaneous Property in Section		S		T		R	
		S		T		R	

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Mar. 8, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9								●					
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-9 - GLO - Set Post - J. Mullett - 1846
 W. Pine 20" S16°W 19 L.
 W. Pine 12" N37°E 26 L.
 - CCC Notes - 1930's. West between Sec. 23 & 26. 160.00 - Set Random post. North between Sec. 26 & 27 - N. 159.06 - Intersect. 2.41 E. (of Random) post E-W.
 N 160 - Set Random post.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-9 - Section Corner common to Sections 22, 23, 26 & 27 - Searched area for GLO evidence but nothing conclusive found. Set 4" DNR Aluminum Cap on 1" x 36" galvanized iron pipe by Double Proportion to GLO between reestablished 'I-11', and Fd. 'F9', 'I-7' & 'M9'. Corner falls 4± South of SW - NE old logging Rd. DNR monument is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 - 4" DNR Aluminum Cap, stamped, on 1" x 36" galv. iron pipe.
 Set Blue Carsonite Post 1' West.
 S24°W 26.40' to set N & T in NW side 3" Cherry
 S77°E 44.57' to set N & T in S. side 3" Red Pine
 N55°E 119.74' to set N & T in NW side 9" Red Pine scribed 'XBT'
 N68°W 100.07' to set N & T in NE side 2" Red Pine.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007