

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Gladwin</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>2E</u>	<u>I-11</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Craig W. McVean, in a field survey on Sept. 13, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-11 - GLO - Set Post - J. Mullett - 1846  
Cedar 8" N18°E 16 L.  
B. Ash 12" S80°W 32 L.  
- CCC Notes - 1930's - East Random between  
Sec. 27 & 34 - 80:00 to corner post correct  
North between Sec. 34-35 - 80:00 Set Random post  
Old post is 77 S. and 10 L. W.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-11 - Sec. Corner common to Sec. 26, 27, 34 & 35 - No GLO evidence found. Dug in swamp based on CCC measurements but could not find any evidence of post. Thus set 4" DNR Alum. Cap on 1" x 8' long galv. iron pipe at record CCC distance of 5229.1' North from fd. 'I-13' for latitude. Longitude by single proportion to CCC distances from fd. 'G11' East 5274.96' - M vs. 5280' - CCC to 'I-11' and East from 'I-11' - 10504.38' - M vs. 10514.46' - CCC to 'M11'. This position fits centerline of E-W gravel road to the West if extended E'ly. N20°W 30' to centerline Gravel Road. DNR Mon. accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 - 4" DNR Alum. Cap on 1" x 8' long galv. iron pipe - Up 1.4'  
Set Blue Carsonite Post 1' N  
S20°E 5.93' to set N & T in E. side 7" R. Maple  
S66°W 21.58' to set N & T in S. side 8" R. Maple  
N70°E 11.85' to set N & T in N. side 5" Elm  
S63°E 22.82 to set N & T in N. side 3" R. Maple



Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 5/9/2007