

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

| | | |
|---|--------------------------|---------------|
| For Corners In: <u>Gladwin</u> (County) | Located In | Corner Code # |
| 1. Public Land Survey | T <u>20N</u> R <u>2E</u> | <u>K13</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 3, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

K13 – GLO – Set Post – L. Clason – 1837
 S. Maple 6" N63°E 8 L.
 W. Pine 24" NW 49 L.
 - CCC – 1930's – on N. Bdy of Sec. 1, T19N, R2E – 80 set random mile post.
 Sec. post is 49 N. and 9 Link E. of random.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K13 – Standard Corner common to Sec. 35 & 36, T20N, R2E – Fd. 2 – 1 1/2" iron pipes lying in swamp but disturbed and not in position, probably removed by timbering. Could not recover old location. No conclusive GLO evidence. Thus set 4" DNR Alum. Cap on 1" x 6' long galv. iron pipe by single proportion to GLO between Fd. CCC positions at 'I-13' and 'L-13'. From this position found 2 W. Pine Stp. remains as follows – N78°W 30' to centerline remains 30"± WPS and N20°W 29.8' to centerline remains 24" WPS ± remains. It is possible one of these WPS's is the GLO BT. DNR Mon. accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K13 – 4" DNR Alum. Cap on 1" x 6' long galv. iron pipe
 East 6.61' (6.6' – GLO) to 'K1', T19N, R2E – DNR Mon.
 N43°E 81.19' to set N & T in side 28" Oak
 S16°E 85.43' to set N & T in side 4" Cherry
 N80°W 172.88' to set N & T in side 8" Maple
 Set Blue Carsonite Post 1' N.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007