

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Gladwin</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>2E</u>	<u>L9</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on Feb. 22, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

L9 – GLO – Set ¼ Post – J. Mullett – 1846  
W. Pine 16" S67°E 13 L.  
Maple 14" N28°W 12 L.  
- CCC Notes – 1930's –  
West 40:00 – Set random ¼ Post  
Pineland  
- Rec. Survey – L. 1, p. 240 – S. S. Barnett – 1973  
No ¼ Corner shown. Iron's along Sec. line only.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L9 – ¼ Corner common to Sec. 24 & 25 – No GLO evidence. Set 4" DNR Alum. Cap on 1" x 36" galv. iron pipe with 4" PVC x 1' casing w/ concrete around cap by single proportion to GLO. This DNR Mon. doesn't agree with section line shown on Barnett Survey since we rejected his positions at 'K9' and 'M9'. Centerline of E-W 2-track is 8.5' South. DNR Monument accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L9 – 4" DNR Alum. Cap on 1" x 3' long galv. iron pipe with 4" x 1' long PVC w/ concrete around cap.  
Set Blue Carsonite Post 1' South  
S70°W 73.72' to set N & T in N. side 15" Tw. R. Maple  
S54°W 120.62' to set N & T in NW side 9" W. Pine scribed 'XBT'  
S3°W 100.05' to set N & T in E. side 10" Oak scribed 'XBT'  
N53°W 71.66' to set N & T in NW side 14" Tamarack  
S25°29'W 32.22' to Fd. 'T' iron with cap #16923



Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 5/9/2007