

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Gladwin Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey		T _____	R _____	
		T _____	R _____	_____
2. Property Controlling in Section	S <u>29</u>	T <u>20N</u>	R <u>2E</u>	<u>5</u>
	S <u>29</u>	T <u>20N</u>	R <u>2E</u>	<u>11</u>
3. Miscellaneous Property in Section	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Mar. 21, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

5 - None

11 - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

5 - CN 1/16 corner, Section 29, T20N, R2E -  
 Set stamped 2" Aluminum cap on 5/8" x 34" rebar per Standard BLM procedure.

11 - SW 1/16 corner, Section 29, T20N, R2E -  
 Set stamped 2" Aluminum cap on 5/8" x 34" rebar per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5 - Stamped 2" Aluminum cap on 5/8" x 34" rebar  
 Set Blue Carsonite Post w/ location tag 1' NE  
 South 18.27' to set N & T in W. side 8" R. Maple  
 S47°W 41.89' to set N & T in NW side 10" Oak  
 N48°W 49.93' to set N & T in NE side 6" Oak  
 N53°W 32.34' to set N & T in S. side 5" W. Pine

11 - Stamped 2" Aluminum Cap on 5/8" x 34" rebar.  
 Set Blue Carsonite Post with location tag 1' SE  
 N48°E 18.89' to set N & T in SE side 8" Oak  
 S77°E 29.34' to set N & T in N. side 2" W. Pine  
 S6°E 43.63' to set N & T in E. side 3" Oak  
 N60°W 24.11' to set N & T in SW side 5" Red Maple

Signed by: \_\_\_\_\_

Craig W. McVean

Surveyor's Michigan License No.: 39088

Date: 5/9/2007

