

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Gladwin Located In Corner Code #
 (County)

1. Public Land Survey	T _____	R _____		
	T _____	R _____		
2. Property Controlling in Section	S <u>32</u>	T <u>20N</u>	R <u>2E</u>	<u>11</u>
	S <u>32</u>	T <u>20N</u>	R <u>2E</u>	<u>12</u>
3. Miscellaneous Property in Section	S _____	T _____	R _____	
	S _____	T _____	R _____	

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on March 22, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

11 - None 12 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p><u>11</u> – SW 1/16, Sec. 32 – Set stamped 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure. Cor. of a single strand fence N & W is 86'± N. and 37.5' ± E.</p>	<p><u>12</u> – CS 1/16 Cor. – Sec. 32 – Set stamped 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure. Centerline of Bulldozed Trail E. is 6'± N. A concrete filled 55 gal. barrel bears N26°E 14'±.</p>
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><u>11</u> – Stamped 2" Alum. Cap on 5/8" x 34" iron rebar. N80°W 46.44' to set N & T in N. side Tri. 8" R. Maple North 26.75' to set N & T in E. side Tw. 12" R. Maple N55°E 48.15' to set N & T in SE side 8" R. Maple S60°E 47.56' to set N & T in SW side 8" R. Maple Set Blue Carsonite Post with loc. tag 1' NE</p>	<p><u>12</u> – Stamped 2" Alum. Cap on 5/8" x 34" iron rebar. Set Blue Carsonite Post with loc. tag 1' N. S14°W 44.50' to set N & T in E. side 12" R. Maple N54°W 31.38' to set N & T in NE side 3" Oak N15°E 29.07' to set N & T in W. side 6" R. Maple S86°E 33.49' to set N & T in S. side 14" R. Maple</p>
--	---

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007