

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Gladwin Located In Corner Code #
 (County)

1. Public Land Survey	T	<u> </u>	R	<u> </u>	<u> </u>
	T	<u> </u>	R	<u> </u>	<u> </u>
2. Property Controlling in Section	S	<u>32</u>	T	<u>20N</u>	R <u>2E</u> <u>13</u>
	S	<u>32</u>	T	<u>20N</u>	R <u>2E</u> <u>16</u>
3. Miscellaneous Property in Section	S	<u> </u>	T	<u> </u>	R <u> </u>
	S	<u> </u>	T	<u> </u>	R <u> </u>

4. Lot No: Recorded Plat:

5. Private Claims:

I, Craig W. McVean, in a field survey on March 22, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

13 - None 16 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p><u>13</u> - SE 1/16 Cor. - Sec. 32 - Set Stamped 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure. Cor. of Old Bulldozed Trail and Berm to W & S. is 10.5' ± N & 11' ± E. A concrete filled 55 gallon barrel bears N72°E 39' ±.</p>	<p><u>16</u> - E. 1/16 Cor. common to S. Line Sec. 32, T20N, R2E - Set stamped 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure. Centerline of E-W Gravel Rd. is 1' ± N. Centerline of 6' ± wide Cut and Berm N. is 14' ± E.</p>
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><u>13</u> - Stamped 2" Alum. Cap on 5/8" x 34" rebar. Set Blue Carsonite Post w/ Loc. Tag 1' NE S8°W 111.47' to set N & T in W. side Tw. 9" R. Maple S30°E 48.25' to set N & T in SW side 11" W. Birch N48°E 29.58' to set N & T in SE side 12" W. Birch N29°W 62.25' to set N & T in W. side 16" R. Maple</p>	<p><u>16</u> - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar - Down 0.5' North 33.00' to set 2" Alum. Cap on 5/8" x 34" rebar on line with Blue Carsonite Post w/ Loc. tag. N28°E 57.47' to set N & T in E. side 12" R. Maple N58°W 74.31' to set N & T in NE side Tw. 12" R. Maple S9°W 67.80' to set N & T in E. side 16" R. Maple</p>
--	---

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/9/2007