

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> N. <u>02</u> S. <u>02</u> R. _____ W. _____	A-6, C-6
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on FEBRUARY 12, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- A-6 RESET W 1/4 COR SEC. 18, T20N, R2W FROM 2 WITS PER L.CAVANAGH CERT OF SURVEY, LIBER 001, PG 780. ALSO FITS J. MEYERS CERT OF SURVEY AND G. DELAMATERS CERT OF SURVEY LIBER 001, PG. 20.
 - C-6 FD 2" PIPE PER 2 WITS FROM J. MEYERS, LS #14099, CERTIFICATE OF SURVEY, APRIL 1983 FOR E 1/4 CORNER SEC. 18, T20N, R2W. J.MEYERS FOUND THIS 2" PIPE IN PLACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6	C-6	
DROVE 5/8" X 3/4" REROD W/RLS CAP.	FOUND 2" PIPE.	
*CONC MON N40°W 42.05'	*18" OAK S50°E 52.30'	
*1/2" REROD EAST 64.08'	* 8" OAK N10°E 52.10'	
14" TW OAK S30°W 29.64'	18" OAK S86°W 95.20'	
*CTR B.TOP EAST 31.5' ±	12" OAK S66°W 101.14'	

*PREVIOUS WITNESSES

*J. MEYERS WITS.

SIGNED BY Carl F. Roser 02-13-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

GLADWIN COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

