

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
GLADWIN  
 (County)

Located In: \_\_\_\_\_ Corner Code ##

- |                                    |   |            |   |           |                  |
|------------------------------------|---|------------|---|-----------|------------------|
| 1. Public Land Survey              | T | <u>20N</u> | R | <u>2E</u> | <u>C-1, D-1,</u> |
|                                    | T | _____      | R | _____     | <u>E-1</u>       |
|                                    | T | _____      | R | _____     | _____            |
|                                    | T | _____      | R | _____     | _____            |
| 2. Property Controlling in Section | S | _____      | T | _____     | _____            |
|                                    | S | _____      | T | _____     | _____            |
| 3. Miscellaneous Property in Sec.  | S | _____      | T | _____     | _____            |
|                                    | S | _____      | T | _____     | _____            |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL F. ROSER, in a field survey on OCTOBER 26, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-1

E-1

C-1

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

"B" CONT. - IN CURVE, IS 154'± WEST. LOCAL SUR USED B.SPIKE TO REESTB. (SP ? TO US) N1/4 COR OF S-6, 1950 MSHD SUR SHOW'S FD B.SPIKE 133.42' E OF FD STONE. CLOSING COR (SEC'S 5 & 6) SHOULD BE 2.75 CH'S (181.5') EAST OF SW S-36 (T21N-R1E) PER US GLO SURVEY.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1

E-1

C-1

REESTABLISHED N 1/4 COR S-5 MIDWAY AND ON LINE BETWEEN NE & NW SEC COR'S OF S-5. OLD FN CORNER (E-W B.WIRE & MOVEN WIRE SOUTH) IS 25'± W AND 20'± N. E-W TRAIL IS ON NORTH SIDE OF FN. COR OF DEEP DRAINAGE DITCH (DITCH S & W) IS S45°W, 90'± 3'.

REESTABLISHED NE COR S-5 AT INTER OF LINE BTW. ESTABLISHED SW & SE COR'S OF S-31 (T21N-R2E) & ON AVERAGE LINE OF B.WIRE FENCE REMAINS TO SOUTH. THIS FITS PROPORTIONATE MEAS. TO U.S. G.L.O. 1 MILE N & 1 MILE S. FENCE COR (FN REMAINS S & W) IS 10' SOUTH.

REESTAB. NW COR OF S-5 AT INTER OF TWP. LINE, BETWEEN S1/4 COR & SW COR OF S-36, T21N-R1E AND LINE BTW. FD PK (IN B.TOP RD INTER OVER STRONG MAG DIP, 2150' SOUTH, POSS SW S-5) & FD BOAT SPIKE 1.94' SOUTH. THIS IS IN LINE W/CTR OF B.TOP RD SOUTH & 15' N OF B.TOP RD FOR 135'± W & 10'± N OF CTR OF GRAVEL RD LOOKING TO EAST. CTR OF M-30 --CONT ABOVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1

E-1

C-1

SET DNR MON & CEDAR POST.

SET DNR MON & CEDAR POST.

DROVE 1"x 27" GALV. PIPE W/PS CAP.

3" ASH S30°E 13.26'  
 9" CEDAR S25°E 45.00'  
 15" CEDAR S20°W 44.30'  
 DNR MON S 1/4 S-36,  
 T21N-R1E S88°11'W 187.29'

7" MAPLE S35°E 30.82'  
 3" ASH S05°W 12.28'  
 6" MAPLE S25°W 22.24'  
 3" MAPLE S86°W 18.55'  
 DNR MON SW S-31,  
 T21N-R2E S88°06'W 241.20'

12" MAPLE S45°E 63.66'  
 17" R.PINE S35°E 93.25'  
 POWER POLE N60°W 84.69'  
 FD BOLT IN MON BOX FOR SW COR S-36, T21N-R1E S88°11'W 133.37'



Signed by Carl F. Roser

Date 9-27-95

Surveyor's Michigan License No. 12028