

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**GLADWIN**  
 (County)

Located In: Corner Code #

1. Public Land Survey	T	<u>20N</u>	R	<u>2E</u>	<u>F-7, 6-7</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	<u>15</u>	T		<u>3,</u>
	S	<u>16</u>	T		<u>12</u>
3. Miscellaneous Property in Sec.	S		T		
	S		T		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL F. ROSER, in a field survey on SEPTEMBER 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(NO EVIDENCE OF G.L.D. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.D. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

"B" CONTINUED:  
 S'LY EDGE TITTABAWASSEE RV.  
 IS 300'± NORTH. E-W TRAIL  
 IS 168'± SOUTH.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<b>F-7</b> FD 3/4" REROD FOR S 1/4 COR S-16. COR FITS TWO G.HENNING WITS (HENNING SAID "SET 5/8" X 3/8" BAR"). WE FD 3/4" X 22 1/2" REROD. HENNING SET COR FROM DBT-W.PINE STP, S66°E 13.69'. WE MEAS S70°E, 13.9' TO OLD AXE NOTCH ON 30" W PINE STP. (MEAS 13.2' TO NEWER FACE SCRIBED "MBT"). US= W.PINE 20, S69°E, 21 (13.9'). (CONTINUED IN "A")	<b>6-7</b> FD 1/2" REROD IN CTR OF GRAVEL RD IN CURVE (NE-SW) FOR SE COR S-16. COR IS IN LINE WITH CENTER OF GRAVEL ROAD LOOKING TO EAST AND CTR OF TRAIL TO SOUTH. FITS OLD, RLS, GEO. HENNING SUR. OF S-16.	<b>3</b> ESTABLISHED NW COR OF SW 1/4 OF NW 1/4 S-15 PER STANDARD BLM INSTRUCTIONS. EAST EDGE OF TITTABAWASSEE RIVER IS 57'± WEST.	<b>12</b> FD 3/4" ROD (WITH 1/4" THICK BY 1 1/4" DIAMETER DISK ON TOP) FOR SE COR OF N 1/2 OF SW 1/4 S-16 AS SET BY G.HENNING. COR FITS ONE FD HENNING WIT; ASPEN SW 7.17'. (WE MEAS 6.8' TO OVERGROWN FACE SCAR.)
---	--	---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<b>F-7</b> FD 3/4" REROD. REPLACED W/DNR MON. SET CED POST.	<b>6-7</b> FD 1/2" REROD. ADDED 1" X 14" GALV PIPE W/RLS CAP.	<b>3</b> DR 5/8" X 3/4" REROD W/RLS CAP. SET CED POST W/LOC TAG.	<b>12</b> FD 3/4" ROD WITH 1/4"x 1 1/4" DISK ON TOP, SET CED POST W/LOC TAG.
10" TWIN MAPLE N30°W 27.2'	9" W PINE N75°E 133.36'	3" W PINE N15°W 14.1'	7" W PINE N15°W 13.5'
8 1/2" ASPEN N35°E 15.38'	8 1/2" TWIN DAK S30°E 33.88'	14" R PINE N65°E 34.9'	7" TWIN W PINE N50°E 21.7'
5" W PINE S15°W 65.6'	8 1/2" W PINE S20°W 61.03'	3" W PINE S65°E 32.7'	4" W PINE S65°E 15.0'
6" MAPLE S55°W 27.3'	CTR SW'LY END 12" CMP S25°W 48.9'	9" W PINE SOUTH 41.5'	6" W PINE S40°W 8.2'

3=WIT BY OTHERS.

1=WIT BY OTHERS.

Signed by Carl F. Roser

Date 9-27-95

Surveyor's Michigan License No. 12028

