

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
GLADWIN

(County)

Located In:

Corner Code ~~≠~~

1. Public Land Survey

T 20N R 2E C-5  
 T \_\_\_\_\_ R \_\_\_\_\_ C-6  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S 18 T \_\_\_\_\_ R \_\_\_\_\_ 2, 9  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, CARL T. KIISKILA, in a field survey on DECEMBER 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 C-5 C-6 2

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5	C-6	2	9
FD AND ACCEPTED 1/2" REBAR LOCATED AT THE INTERSECTION OF N-S ROAD AND RD TO WEST. THIS IRON FITS A SURVEY DONE BY G. HENNING IN 1967 FOR S-18 AND ALSO A 1992 SURVEY BY P. LAPHAM IN S-17.	REESTAB'D THE E 1/4 COR OF SEC 18 MIDWAY AND ON LINE BETWEEN FD SECTION CORNERS WHICH AGREES WITH G. HENNING'S SURVEY DONE IN SECTION 18. CTR OF N-S RD IS 3' EAST.	ESTAB'D THE NE COR OF NW 1/4 OF THE NE 1/4 SEC 18 BY STANDARD PROCEDURE FOR SUBDIVISION OF A SECTION.	ESTABLISHED THE SE COR OF THE SW 1/4 OF THE NE 1/4 SEC 18 BY STANDARD PROCEDURE FOR SUBDIVISION OF A SECTION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5	C-6	2	9
FD 1/2" REBAR AT INTERSEC OF WILDWOOD & DRUMMOND RDS.	SET 5/8" X 16" REROD W/ CAP.	SET 5/8" X 34" CAPPED REROD.	SET 3/4" X 48" IRON PIPE W/ CAP & CED POST.
**POWER POLE N43°W 44.62'	FD CUT NAIL N20°E 11.36'	8" J PINE N19°E 51.61'	14" ASH SOUTH 29.96'
8" ASH S55°W 69.60'	CED POST(W/PK) N85°W 19.00'	8" ASH N37°E 69.16'	8" ASH N73°W 23.98'
#10" ASH S63°E 37.15'	POPLAR S84°E 45.23'	5" SPRUCE S48°W 37.56'	6" ASH N07°E 4.74'
#16" ASH N50°E 68.17'	CTR OF N-S RD EAST 3.0'	3" SPRUCE S32°E 54.64'	8" ASH N85°E 11.19'
		CTR E-W ROAD SOUTH 4'	UPPER BLAZES & SIDE NAILS.
		CEDAR POST SOUTH 33'	

\*OLD WITNESSES.  
 \*\*=E. GOSS, RLS#16040 WIT.

Signed by Carl T. Kiiskila

Date 1-23-96

Surveyor's Michigan License No. 33981

