

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Gladwin County Remonumentation

1987 001 PAGE 34

For Corners in  
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 20N R. 2W A-9  
T. \_\_\_\_\_ R. \_\_\_\_\_  
T. \_\_\_\_\_ R. \_\_\_\_\_
- 2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

10 AUG 2000 11:27:59 AM

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson  
Set Post for Cor of Sec's 24 & 25  
Wit-(1)Beech 10 S36W 21  
(2)Do 6 N20W 03

1989 Lapham--survey  
Found Bar  
Wit-same as (3), (4) & (5)

1979 Sedgman--LCRC#231 & survey  
Found 1/2" Bar  
Wit-(3)N72°E 45.40' 6" Maple  
(4)N71°E 60.90' Tele. Pole  
(5)S49°E 86.90' Power Pole  
Same wits 1972 LCRC#76-72 Ostling

1992 Lapham--working drawing  
Wit-none

1993 Erickson  
LCRC#350 & working drawing  
Found 1/2" Bar  
Wit-(6)N65W 60.75' Telephone Pole  
(7)N78E 45.47' 12" Maple  
(8)S43E 87.16' Power Pole  
(9)S39W 67.13' 10" Maple

1972-97 Clare County Records  
LCRC & 6 surveys  
Wit-same as (3), (4) & (5)

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 8-9-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" bar in 3/4" pipe in monument box in centerline highway opposite centerline of road to West. Agrees with witnesses (4)Recorded 60.9; measured 60.86'; (3)Recorded 45.40'; measured 45.45'. Agrees with measurements to A-8 by Ostling (1972) 2682.2' & Lapham (1992) 2685.70'. Accepted found 3/4" pipe as corner of record.

See dossier for detailed report on corner A-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Gladwin Remonumentation cap marked P.S. 27458 on found 3/4" pipe in Monument Box. Accepted as best available evidence to perpetuate position of corner A-9.

Witnesses:

- N71°W Tele. Pole, nail & tag, 60.86' (OBT)
- N72°E 12" Triple Maple, nail & tag, 45.45' (OBT)
- S43°E Power Pole, nail & tag, 87.64' (NBT)
- S45°W 16" Maple, nail & tag, 83.15' (NBT)
- N22°W 12" Twin Maple, nail & tag, 80.68' (NBT)

Signed by [Signature]  
Surveyor's Michigan License No. 27458

Date 8-9-00

