

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 340

For Corners in
GLADWIN
(County)

Located In: Corner Code#:

- 1. Public Land Survey T. 20N R. 2W A-13
T. _____ R. _____
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION
10 AUG 2000 11:27:48 AM
BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson
Wit-B. Ash 8" N25E 08
B. Ash 9" S51W 03

3-11-77 Meyers
Unrecorded survey
Set R.R. spike
Wit-N45E 87.13 P.P.
S45W 80.77 P.P.
S30W 41.47 Ced. Post

3-15-80 Sedgman--Sketch of survey
Sec 31, T20N, R2W Gladwin Co.

4-25-08 Johnson CSR 4-135 & 5-73
All Gov't Cors Fd
Wit-Pine Stp. 28" N7W 79
Tel. Pole 8" N43 1/2E 51 1/2

8-14-79 Sedgman, R.R. Spike
Wit-N40E 87.03 P.P.
S35E 80.73 P.P.
N65W 81.95 T.P.

4-18-90 Wilcox LCRC#606
Set 1/2" rebar
Wit-West 8.0 C.L. road to North
N45E 87.10 P.P.
S10W 72.92 4" Elm
South 33.05 3/8" Rebar

1955 Moore--Gladwin Co.
Plat of Miller Subd--Sec 6, T19N, R2W

Recorded in LCRC 250-97 Clare County Recon

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found Clare County Remon in Monument box. Agrees with recorded witnesses in LCRC#250-97 Clare Co., Michigan Public Records. Accepted as corner of record.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

See dossier for detailed report on corner A-13.

Co. Rep. [Signature]
Date 8-9-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Found 5/8" x 36" rod with Clare Co. Remon cap marked P.S. 27458 in Monument Box. Accepted as best available evidence to perpetuate position of corner A-13.

- Witnesses:
- N67°E 131.60', nail & tag, 10" Elm
 - N17°E 111.02', South end 24" C.M.P.
 - N45°E 84.90', nail & tag, P.P.
 - N24°W 74.66', Center of Tele. Riser
 - S34°E 78.80', nail & tag, P.P.



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00