

REMONUMENTATION

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 328

For Corners in
GLADWIN
(County)

Table with 3 columns: Located In, Corner Code#, and 5 rows of survey types (Public Land Survey, Public Controlling in Section, Miscellaneous Property in Section, Lot No., Private Claims).

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:24:24 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo Adair
Set QR. Post
Wit-(1)Beech 7 N34 1/2E 24 lks
(2)Maple 9 S27W 31 lks

1984 Lapham--survey & wits
Set C.I.
This corner set incorrectly--and removed
by Lapham.

1993 Erickson
LCRC#350, survey & wkg dwg
Set 1/2" Rebar with Cap
Wit-(3)N54W 46.92' N&T Triple 10"
Maples
(4)N51E 63.31' N&T 22" Oak
(5)S52E 37.15' N&T 8" Maple
(6)S61W 21.47' Nail 19" Oak

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found capped iron#29245 15 feet South of trail road to West and 3 feet West of North-South trail road. Agrees with Erickson's witnesses (3 & (6).

See dossier for detailed report on corner B-9.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 6-15-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rod with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner B-9.

Witnesses:
N54°W Triple Maple, nail & tag, 46.92' (OBT)
S61°W 19" Oak, nail & tag, 21.47' (OBT)
N50°E 36" Oak, nail & tag, 63.00'
S50°E 12" Maple, nail & tag, 37.40'



Signed by [Signature] Date 8-9-00
Surveyor's Michigan License No. 27458