

AUG 23 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Gladwin County Remonumentation

11952 001 PAGE 324

For Corners in  
GLADWIN  
(County)

Located In: Corner Code#:

1. Public Land Survey T. 20N R. 2W C-7  
T. \_\_\_\_\_ R. \_\_\_\_\_  
T. \_\_\_\_\_ R. \_\_\_\_\_

2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_

3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION  
10 AUG 2000 11:23:42 AM  
BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo Adair Set Post Wit-none	1992 Lapham LCRC#344 & wkg dwg Found P.K. Nail over iron Wit-(4) West, Power Pole, 32.20' (5)N30°W, Top Center, 12" CMP 42.08' (6)N30°E, Top Center, 16" CMP 75.20' (7)S35°E, 12" W. Oak. 73.62'	1996 County Road Commission Set P.K. nail Wit-same as (4), (6), (7) & (8)S70E 16" W. Oak, N&T, 83.10' (NBT)
1954 Ostling--Found 1" Pipe		
1969 Plat Grass Lake Estates		
1979 Lapham Found 1" Capped Iron Wit-(1) West, 33.20' - Corner Post (2)N35°W, 57.60' - 6" Post (3)N75°E, 30.25' - 6" Poplar	1994 Lapham survey & working drawing Wit-same as (4), (5), (6) & (7)	

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County  
Co. Rep. [Signature]  
Date 8-9-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found P.K. nail & tag over 1" iron one foot West of centerline North-South road opposite fence to West. Agrees with survey by Lapham (1979)--found 1" pipe 33.00 West. Also agrees with witnesses (4), (6) & (7), and measurement to D-7 by Ostling (1954) 2670.0' & Lapham (1994) 2669.82'. Accepted found P.K. nail and 1" iron as corner of record; replaced with 5/8" x 36" rerod.

See dossier for detailed report on corner C-7.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Gladwin Remonumentation cap marked P.S. 27458 in Monument Box. Accepted as best available evidence to perpetuate position of corner C-7.

Witnesses:  
West, 1" Iron Pipe, 33.00' (NBT)  
N68°W 28" Oak, nail & tag, 83.10' (OBT)  
S70°E 16" White Oak, nail & tag, 83.10' (OBT)  
West, Power Pole, nail & tag, 32.20' (OBT)  
S35°E 14" White Oak, nail & tag, 73.62' (OBT)  
North & East, P.K. nail, 2.0'



Signed by [Signature]  
Surveyor's Michigan License No. 27458

Date 8-9-00