

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 332

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 20N R. 2W C-11
T. _____ R. _____
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:25:51 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo Adair
Set Post at Cor of Sec's 29, 30, 31, 32
Wit-(1)Hemlock 11 N49E 20 lks
(2)Hemlock 9 S45W 10 lks

1981-95 Lapham
3 surveys, & working dwgs
Found 1" Bar
Wit-same as (3), (4) & (5)

1998 Lapham
Found R/R spike
working drawing

1978 Sedgman
LCRC#159, survey & working drawing
Found 1" Iron
Wit-(3)S25°W 41.14' 12" Tree
(4)S50°E 62.72' Power Pole
(5)N50°E 39.33' Street Sign Post

1993 Erickson
LCRC#351 & working drawing
Found railroad spike
Wit-(6)N49E 93.31' SW Cor Metal Gar
(7)S50E 62.69' N&T Power Pole
(8)S49W 107.63' N&T Power Pole
(9)N42W 210.95' N&T Power Pole

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. Mark R. Robison
Date 6-15-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found railroad spike intersection of crossroads. Agrees with witnesses (4), (6) & (9). Agrees with measurements to B-11 by Sedgman (1977) 2637.40' & Lapham (1998) 2637.64' and also agrees with measurements to C-12 by Sedgman (1976) 2699.56' & Lapham (1995) 2699.58'. Accepted found railroad spike as corner of record; replaced with 5/8" x 36" rerod.

See dossier for detailed report on corner C-11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Gladwin Remonumentation cap marked P.S. 27458 in Monument Box. Accepted as best available evidence to perpetuate position of corner C-11.

Witnesses:
S50°E Power Pole, nail & tag, 62.72' (OBT)
N49°E SW Corner Metal Shed (base) 93.22' (OBT)
N42°W Power Pole, nail & tag, 210.90' (OBT)
S45°W 6" Tree, nail & tag, 81.00' (NBT)
North & East, P.K. nail, 2.0'



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 8-9-00