

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Gladwin County Remonumentation

LIBER 001 PAGE 292

For Corners in  
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 20N R. 2W D-7  
T. \_\_\_\_\_ R. \_\_\_\_\_  
T. \_\_\_\_\_ R. \_\_\_\_\_
- 2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

10 AUG 2000 11:15:52 AM

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on June 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson  
Set QR. Sec Post  
Wit-(1)  
(2)

1957 Plat of Island Lake subd  
Ostling Set Conc. Mon.  
Wit-(4)W. Oak 20" N 14½ E  
22.00'  
(5)B. Oak 8" N71W 51.00'  
& Ostling survey report

1993 Lapham--wkg dwg/section subd  
Found Conc Mon  
Wit-none

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

No corner found, destroyed by Grass Lake lot owner through construction of new well and well pit. Set corner from Lapham (1993) field notes, 10.1' South of 8' high division fence between Island Lake and Grass Lake Subdivisions. Corner more or less M.P.O.L. per Lapham (1993) survey and Ostling survey., Accepted reset corner as corner of record; set 5/8" x 36" rerod.

See dossier for detailed report on corner D-7.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 6-15-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner D-7.

Witnesses:

- N15°E 28" Oak, nail & tag, 22.4' OBT
- N45°E 12" Oak, nail & tag, 47.42'
- S75°W 20" Oak, nail & tag, 41.75'
- East, NW Corner Cabin, 16.00'



Signed by [Signature]  
Surveyor's Michigan License No. 27458

Date 8-9-2000