

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 322

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 20N R. 2W E-6
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No., Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:23:19 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo Adair
Set QR. Sec. Post
Wit-(1)Cedar 11 N50 1/2W 37 lks
(2)W. Pine 28 S54E 9 1/2 lks

1985 Lapham
working drawing
Wit-none

1985 Clifford--unrec. LCRC & wkg d

1954 Robert Ostling
Found SQ. Post 2' East of Fence line
Wit-none

1961 DNR
Found old Squared Post in Swamp at
Fence line from South
Set 1" Pipe with 4" Brass Cap
Wit-(3)6" Cedar - S21E - 36.5 feet
(4)14" Cedar - S87E - 85.7 feet

1994 Lapham
Found D.N.R. Monument
Wit-(5)S30°E, 30.65' - 10" Cedar
(6)N30°E, 30.90' - 5" Birch
(7)N50°W, 22.65' - 5" Birch

1959 DNR
Found old Squared Post in Swamp

1997 Lapham
Wit-same as (5), (6) & (7)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found D.N.R. survey monument (1" pipe with 4" brass cap) in North-South old fence (down) in swamp. Agrees with Clifford & Lapham witnesses. Accepted found monument as corner of record.

See dossier for detailed report on corner E-6.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 8-15-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found D.N.R. 1" pipe with 4" brass cap. Accepted as best available evidence to perpetuate position of corner E-6.

- Witnesses:
S30°E 30.65', nail & tag, 12" Cedar (OBT)
N30°E 5" Birch Stub, spike, 30.90' (OBT)
N10°W 6" Ash, nail & tag, 32.70'
N40°E 5" Ash, nail & tag, 30.82'
S10°W 3" Ash, nail & tag, 4.10'



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00