

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 336

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 20N R. 2W E-11
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No., Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:26:40 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-L and rows 1-13. A dot is present at row 11, column C.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo Adair
Set Post at Cor Sec's 28, 29, 32 & 33
Wit-(1)W. Pine N17W 14 lks
(2)W. Birch 12 S66 1/2E 18 lks

1981 Lapham--survey
Found Capped Iron R.L.S.
Wit-(3)N45°E Fence Cor. 43.30'
(4)N45°W Tele. Pole 33.00'
(5)S45°W Fence Cor. 49.25'

1984 Lapham LCRC#287
Found C.I.
Wit-same as (3), (4) & (5)

1976 Sedgman--field notes
Set nail in intersection of center-lines

1983 Lapham--survey
Found C.I.
Wit-same as (3), (4) & (5)

1987 Lapham
Found C.I.
Wit-same as (3), (4) & (5)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 18" reroed in intersection of roads. Agrees with witnesses (3) & (5). Also agrees with Lapham (1984) measurement 2652.06' and Sedgman (1976) measurement 2652.31' to D-11. Accepted found iron as corner of record; replaced with 5/8" x 36" reroed.

See dossier for detailed report on corner E-11.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 6-15-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" reroed with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner E-11.

Witnesses:

- S45°W Fence Corner, nail & tag, 49.20' (OBT)
S50°E 12" W. Pine, nail & tag, 63.85'
N60°E 16" Poplar, nail & tag, 84.95'
N45°E 16" W. Pine 88.55'
N45°E Fence Post, nail & tag 43.3' (OBT)



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00