

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 342

For Corners in
GLADWIN

Form with fields: (County), Located In: T. 20N R. 2W, Corner Code#: K-1, 1. Public Land Survey, 2. Public Controlling in Section, 3. Miscellaneous Property in Section, 4. Lot No., 5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:28:09 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13 containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson
Set Post Sections 35 & 36
Wit-(1)Yellow Pine 14 N55E 143
(2)White Pine 36" N68W 89

1987 Lapham
survey & working drawing
Set C.I., double over N1/4 Corner
Wit-(3)East 24" Oak 4.90'
(4)N45E 5" Maple 12.00'
(5)South 8" Maple 16.40'

1990 North Central
survey & survey report
Found 1/2" Iron
Wit-none

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found capped iron 45 feet East of fence corner, 10" high, fences North-South. Found witnesses (3)24" Oak stub, 4+/- East of corner & (5)Recorded & measured 16.4', blazed, no witness tags. Corner accepted in 1990 survey by North Central. Accepted found capped iron as corner of record; replaced with 5/8" x 36" rorod.

See dossier for detailed report on corner K-1.

Co. Rep. [Signature]
Date

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rorod with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner K-1.

Witnesses:
South 8" Maple, nail & tag, 16.40' (OBT)
S85°E 10" Maple, nail & tag, 27.00' (NBT)
N40°E 14" Oak, nail & tag, 36.82' (NBT)
N35°W 24" Oak, nail & tag, 32.02' (NBT)



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00