

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

1987 301 PAGE 343

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 20N R. 2W K-2
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:28:20 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on February 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell (2,8) contains a dot.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo Adair Set QR. Sec. Post Wit-(1)W. Pine 24 N64E 20 (2)W. Pine 24 S24 1/2W 28
1989 Lapham survey & working drawing Set C.I. (R.L.S.) Wit-(3)N10°W 16" Maple 58.45' (4)S70°W 12" Twin Maple 25.90' (5)S35°W 20" W. Oak 47.50' Corner set at prorated distance between NW & SW Corners

1990-93 Lapham--surveys Wit-same as (3), (4) & (5) APPROVED LAND CORNER P.A. 345 of 1990 Gladwin County

Co. Rep. [Signature] Date 6-2-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 18" capped iron (Lapham) 20'+/- South of trail road and 100 feet West of opening and one-track trail to North. Agrees with witnesses (3) & (4). Accepted found 1/2" iron; replaced with 5/8" x 36" roerd.

See dossier for detailed report on corner K-2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" roerd with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner K-2.

Witnesses: South 5" Oak, nail & tag, 3.78' (NBT) S70°W Twin 12" Maple, spike, 25.92' (OBT) S35°W 24" W. Oak, nail & tag, 47.44' (OBT) S20°E Twin 14" Maple, nail & tag, 28.12' (NBT) N70°W 18" Maple, spike, 58.45'



Signed by [Signature] Date 8-9-00
Surveyor's Michigan License No. 27458