

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

11RFR 001 PAGE 345

For Corners in
GLADWIN
(County)

Located In: Corner Code#:

- 1. Public Land Survey T. 20N R. 2W L-1
2. Public Controlling in Section S. T. R.
3. Miscellaneous S. T. R.
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:28:41 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13 containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson--Set QR. Post
Wit-(1)Hemlock 12 N72W 10
(2)Beech 9 S6E 21

1990 North Central
survey & survey report
Found 1/2" Iron
Wit-none

1987 Lapham
survey & working drawing
Set C.I. opposite fence to South in
Centerline of County Road
Wit-(3)South spike in P.P. 37.00'
(4)N45°E 6" W. Pine 57.13'
(5)N60W 4"x4" Gate Post (West)
57.00'

1994 Lapham--survey
Found C.I.
Wit-same as (3), (4) & (5)

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 6-27-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" capped iron 3 feet North of centerline East-West road opposite fence to South. Agrees with found witnesses: (3)Recorded 37.00', measured 37.05'; (5)Recorded 57.00', measured 56.95'. Corner agrees with survey by North Central in Roscommon County. Replaced found 1/2" iron with 5/8" x 36" rerod.

See dossier for detailed report on corner L-1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Gladwin Remonumentation cap marked P.S. 27458). Accepted as best available evidence to perpetuate position of corner L-1.

- Witnesses:
N55°W 14" W. Pine, nail & tag, 74.65'
S50°W 16" Maple, nail & tag, 58.60'
S30°E 12" Apple, nail & tag, 67.42'
N55°E 16" W. Pine, nail & tag, 57.20'
South Power Pole, spike, 37.05' (OBT)
N60°W 4" x 4" Gate Post (West), spike, 56.95' (OBT)



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00