

AUG 23 2000

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 346

For Corners in
GLADWIN
(County)

Table with 3 columns: Located In: (T. 20N R. 2W), Corner Code#: (L-3), and various survey types (Public Land Survey, Public Controlling in Section, etc.)

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION
10 AUG 2000 11:28:52 AM
BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 1-13. A dot is marked in row 3, column J.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 Geo Adair--Set QR. Post
Wit-(1)Aspen 4 N32E 32 lks
(2)Aspen 5 S23W 27 lks
1969 Henning--survey
Set 1/2" Bar
Wit-(3)S.W. Corner House N22°E - 64.7'
(4)N.W. Corner House S25°E - 76.1'
1975 Sedgman--LCRC#133
Set 1/2" C.I. from Henning survey
Wit-(5)S75°W 57.11' 24" Maple
(6)S20°W 16.76' 20" Tree
(7)North 27.96 Tele. Pole
1975 Fluharty--LCRC#139, Fd. Re-rod
Wit-(8)P.P., N06°E, 27.96'
(9)30" Box Elder, S30°W, 16.77'
(10)28" Maple, S80°W, 57.17'

1982 Lapham--survey
Found 3/8" Rod
Wit--same as (5), (6), & (7)
APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 8-9-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Found capped iron 2 feet South of centerline of East-West road opposite fence to North. Corner agrees with witnesses (4), (6), & (7). Accepted found capped iron as corner of record; replaced with 5/8" x 36" rerod.

See dossier for detailed report on corner L-3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner L-3.

- Witnesses:
North Power Pole, nail & tag, 27.92', (OBT)
N30°E 24" W. Pine, nail & tag, 47.20' (NBT)
N65°E 20" W. Pine, nail & tag, 86.12' (NBT)
S25°E N.W. Corner House, block, 76.10' (OBT)
S20W 30" Ash, nail & tag, 17.00'



Signed by [Signature] Date 8-9-00
Surveyor's Michigan License No. 27458