

DEC 16 1996

GLADWIN COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 104

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>2W</u>	<u>M - 10</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

2 DEC 96 3:23 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 GEO E. ADAIR  
SET 1/4 POST  
WIT.-(1)ASPEN 6 S14W 23  
(2)CEDAR 6 N18W 17

1975 PAUL LAPHAM-SECTION SUBD.  
WIT.-NONE

1984 GLADWIN CO. RD. PLANS  
TEE IRON  
WIT.-(3)N35E 58.9 FE. POST  
(4)EAST 33.0 COR POST  
(5)S45E 45.7 FE. POST  
APPROX. 1/4 COR.

1975 PAUL LAPHAM L.C.R.C.#137  
FOUND SUCKER ROD  
WIT.-(7)EAST 33.01 COR POST  
(8)S70E 42.82 2nd POST SOUTH  
(9)S85W 56.70 TELE ROUTE MARKER

1980 PAUL LAPHAM SURVEY  
WIT.-SAME AS (7),(8)&(9)

APPROVED LAND CORNER  
P.A. 345 of 1930  
Gladwin County

Co. Rep. Mark Robison  
Date 11/6/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 12" SUCKER ROD 25' EAST OF C/L OF CURVE IN ROAD ON C/L OF NORTH ROAD EXTENDED SOUTH, OPPOSITE FENCES EAST & WEST. FOUND (7), N&T; REC. 33.01, MEAS. 33.11. FOUND (8), N&T; REC. 42.82, MEAS. 42.76. SET GLADWIN RE-MON IN PLACE OF FOUND SUCKER ROD.

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10: EAST 1/4 CORNER OF SECTION 25  
SET 5/8" X 36" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458

WITNESSES:  
EAST POWER POLE, N&T, 37.83'  
S50E 3" MAPLE, N&T, 98.20'  
WEST C/L ROAD, P.K. NAIL, 24.83'  
EAST COR POST, N&T, 33.11'  
S70E 2nd POST SOUTH



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 11-29-96