

**MICHIGAN**  
**DEPARTMENT OF CONSERVATION**  
**FORESTRY DIVISION**

# LAND CORNER RECORD

T. 20 N.R. 2 W


Gladwin COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 15 - 16

CORNER MONUMENT 1" pipe with 4" brass cap.

DATE MONUMENT PLACED AND WITNESSED 12-19-61

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

6" Cedar - S 59 W - 7.6 feet

9" Cedar - N 12 W - 10.2 feet

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was set by proportionate measurement, midpoint on line, between section corners. Unable to positively identify U.S.BT's. Falls nearly in line with old N-S fence, at apparent cutting line. About 25 feet south of Meridith grade road.

**SURVEYOR'S SEAL**

SIGNED *Kenneth J. Ostberg* DATE 12/22/61  
REGISTERED LAND SURVEYOR