

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 20 N.R. 2 W


Gladwin COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 16 - 17

CORNER MONUMENT 1" pipe with 4" brass cap.

DATE MONUMENT PLACED AND WITNESSED 12-19-61

WITNESSES TO CORNER.....



6" Cedar - S 21 E - 36.5 feet

14" Cedar - S 87 E - 85.7 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey of Section 16. Found very old squared post at fence line from south. Used in subdivision of Section 17. One possible U.S.BT stump in place. Checks acceptably with swamp edge north. Best available evidence.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Betting* DATE 12/22/61
REGISTERED LAND SURVEYOR