

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 20 N.R. 2 W


Gladwin COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 16 - 21

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 12-19-61

WITNESSES TO CORNER.....



9" Tamarack	-	N 79 E	-	19.8 feet
7" Cedar	-	S 85 W	-	27.2 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line, between section corner, while making a survey of Section 16. Unable to identify U.S.BT's, but this point checks swamp and stream edges acceptably.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Osting* DATE 12/22/61  
REGISTERED LAND SURVEYOR