

DEC 16 1996

COMMISSION

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 132

For corners in

Table with columns: GLADWIN (County), Located In: (Town/Range/Section), Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

2 DEC 96 3:30 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, MARK ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numerical data points for survey locations.

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 GEO E. ADAIR SET 1/4 POST WIT.-(1)BEECH 9 N27E 34 (2)DO 6 S25 1/2W 36
1980 KNOX FLOW POINT FOR CORNER 1972 P LAPHAM SVY NO COR. MATERIAL WIT.-(3)S35E 65.72 P.P. (4)S35W 28.9 FE. COR. (5)N55W 53.3 FE. COR.
1970 PAUL LAPHAM-WORKING DRAWING 1974 EDMANDS ENG NO COR MATERIAL WIT.-(6)S45E 63.65 P.P.
(7)W 18.4 TO C/L DRIVE NORTH (8)S45E 23.6 E. END C.M.P (9)S05W 18.4 TO W. END C.M.P
1980 PAUL LAPHAM SURVEY WIT.-SAME AS (8),(9)&(9)
1982 PAUL LAPHAM SURVEY WIT.-SAME AS (6),(8)&(9)
1991 PAUL LAPHAM SURVEY WIT.-SAME AS (6),(8)&(9)
1993 MYERS-SEC. SUBD. WIT.-NONE
1993 PAUL LAPHAM SURVEY

- FOUND 1 1/2" IRON WIT.-(10)S35E 63.62 P.P. (11)S35W 26.4 FE. COR. (12)N50W 53.80 FE. COR.
1995 PAUL LAPHAM SURVEY WIT.-NONE
MISC PAUL LAPHAM-SEC. SUBD.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND P.K. NAIL IN C/L OF ROAD OPP FENCE TO NORTH, SET BY PAUL LAPHAM FROM SURVEY # 8173 & G-956644. FOUND WITNESS (8); REC 63.65, MEAS. 63.45. SET GLADWIN RE-MON FROM SURVEY # 823875 AND FOUND WITNESS (8) AND FOUND P.K. NAIL.

APPROVED LAND CORNER
P.A. 745 of 1990
Gladwin County

SEE DOSSIER FOR DETAILED REPORT.

Co. Rep. [Signature]
Date 11/6/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7: 1/4 CORNER COMMON TO SECTIONS 18 & 19
SET 5/8" X 36" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458 IN MONUMENT BOX.

- WITNESSES:
S35E POWER POLE, N&T, 63.62' N45E 1/2" X 36" REROD 46.60'
N40W 4" ELM, N&T 76.65' NORTH, P.K. NAIL, 2.0'
SOUTH C.I.#9344 33.38' EAST, P.K. NAIL, 2.0'



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 11-29-96