

DEC 16 1996

COMMISSION

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 134

For corners in

GLADWIN

(County)

Located In:

Corner Code #

1. Public Land Survey

T	20N	R	1W	B - 11
T		R		
T		R		
T		R		
S		T	R	
S		T	R	
S		T	R	
S		T	R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

2 DEC 96 3:30 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, MARK ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1856 GEO. E. ADAIR
SET POST
WIT.-(1)B. ASH 6 N7 1/2E 11
(2)B.ASH 5 S85E 17

APPROVED LAND CORNER
P.A. 045 of 1990
Gladwin County

Co. Rep. [Signature]
Date 11/6/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" PIPE 3' NORTH OF C/L IN LINE WITH FENCE TO NORTH IN PRIVATE ROAD 24" BELOW SURFACE--SAME SIZE PIPE AS FOUND AT C-9. SET GLADWIN RE-MON IN PIPE.

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11: 1/4 CORNER COMMON TO SECTIONS 30 & 31
SET 5/8" X 36" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458

WITNESSES:
S80E POWER POLE, N&T, 92.75'
N80E 8" ELM, N&T, 28.12'
N80W 14" ELM, N&T, 37.40'
S60W 5" BASS WOOD, N&T, 69.90'



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-29-96