

# SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

GLADWIN COUNTY REMONUMENTATION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **140**

For corners in

GLADWIN	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T <u>20N</u> R <u>1W</u>	C - <u>10</u>	
	T <u>    </u> R <u>    </u>	_____	
	T <u>    </u> R <u>    </u>	_____	
	T <u>    </u> R <u>    </u>	_____	
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	_____	
	S <u>    </u> T <u>    </u> R <u>    </u>	_____	
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	_____	
	S <u>    </u> T <u>    </u> R <u>    </u>	_____	

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

2 DEC 96 3:31 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

1856 GEO E. ADAIR (5)EAST 30.05 4" PIPE FE POST  
SET 1/4 POST (6)N45E 36.10 FE POST  
WIT.-(1)TAMARACK 7 N19E 10 (7)S70E 33.20 FE POST  
(2)CEDAR 6 S24 1/2W 19

1908 KNOX  
WIT.-(3)CEDAR 3' X 3" X 3"

1978 PAUL LAPHAM L.C.R.C.#207  
SET 1/2" IRON  
WIT.-(4)N60W 37.00 FE POST

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 3/8" X 2' SMOOTH ROD OVER 10" SPIKE, EXCAVATED FOUND 1/2" IRON 30" BELOW ROAD SURFACE 0.2' WEST OF 10" SPIKE IN C/L CO. ROAD ON LINE WITH FENCE TO EAST. FOUND (5) SEPARATE FROM CONC. BASE; MEAS. TO BASE 30.28, REC 30.05. SET GLADWIN RE-MON IN PLACE OF FOUND 1/2" IRON.

SEE DOSSIER FOR DETAILED REPORT.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-10: 1/4 CORNER COMMON TO SECTIONS 29 & 30  
SET 5/8" X 3/8" REROD WITH GLADWIN COUNTY RE-MON CAP MARKED P.S.#27458

WITNESSES:  
EAST METAL POST WHERE ENTERED CONC. 30.28'  
S45W 14" ELM, N&T, 54.68'  
WEST 10" POPLAR, N&T, 41.81'  
N40W 4" ELM, N&T, 48.00'

APPROVED LAND CORNER  
P.A. 74, 1970  
Gladwin County

Co. Rep. John Meyers  
Date 11/6/96



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 11-29-96