

# SURVEY & REMONUMENTATION

DEC 1 6 1996

COMMISSION

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 141

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 1W	C - 11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

2 DEC 96 3:32 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARK ROBISON, in a field survey on November, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 GEO E. ADAIR SET POST WIT.-(1)ELM 17 N33 1/2W 48LKS (2)ELM 15 S63 1/2E 18	1975 PAUL LAPHAM L.C.R.C.#120 FOUND R/R SPIKE WIT.-(3)N45E 39.30 STEEL FE POST (4)N45W 41.25 14" ELM (5)S45E 54.55 T.P.	1992 PAUL LAPHAM SURVEY FOUND R/R SPIKE WIT.-(6)N45E 39.2 STEEL POST (7)S45E 53.30 COR FE POST (8)N50E 47.30 P.P. (9)N45W 75.05 P.P.
1908 KNOX FD OLD STAKE IN NEST OF STONES	1975 PAUL LAPHAM SURVEY WIT.-SAME AS (3),(4)&(5)	
1970 PAUL LAPHAM SURVEY WIT.-NONE	1980 PAUL LAPHAM SURVEY WIT.-SAME AS (3),(4)&(5)	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" X 2' SMOOTH ROD OVER R/R SPIKE 16" BELOW SURFACE OF COUNTY T-ROAD, N-S-E. FOUND (3); MEAS. 39.2, REC. 39.3. FOUND (9); MEAS. 75.10, REC. 75.05. SET GLADWIN RE-MON IN PLACE OF FOUND R/R SPIKE.

APPROVED AND CORNER  
P.A. 74 of 1970  
Gladwin County

SEE DOSSIER FOR DETAILED REPORT.

Co. Rep. John M. [Signature]  
Date 11/6/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11: CORNER COMMON TO SECTIONS 29, 30, 31 & 32  
SET 5/8" X 3/8" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458

WITNESSES:  
N45W POWER POLE, N&T, 75.10'  
N45E STEEL POST TO WELD LINE MARK 39.20'  
N50E SW COR OLD SCHOOL HOUSE, CONC. TRIM, 84.00'  
S45W GUARD POST, N&T, 23.73'



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 11-29-96