

**SURVEY & REMONUMENTATION**

**GLADWIN COUNTY REMONUMENTATION**

**DEC 16 1996**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

001 PAGE 146

For corners in **COMMISSION**

GLADWIN (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>1W</u>	<u>E - 10</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

2 DEC 96 3:33 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1858 GEO E. ADAIR (9)WEST 33.0 COR POST  
SET 1/4 POST  
WIT.-(1)MAPLE 7 N48W 9  
(2)HEMLOCK 6 S61 1/2E 20

1978 PAUL LAPHAM L.C.R.C.#207  
FOUND 2 - 6" STONES SIDE BY SIDE  
SET 3/4" IRON BETWEEN STONES  
WIT.-(3)S55W 36.65 ELM STUMP  
(4)S60E 37.70 FE POST  
(5)EAST 31.2 COR POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON BETWEEN STONES IN C/L OF ROAD N-S, FENCE WEST, FENCE COR EAST. FOUND (4), N&T, IN LOOSE POST; MEAS. 37.85+/-, REC.37.70. FOUND (5); MEAS. 31.15 TO FACE, REC. 31.2. SET GLADWIN RE-MON IN PLACE OF FOUND IRON.

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10: 1/4 CORNER COMMON TO SECTIONS 28 & 29  
SET 5/8" X 38" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458

WITNESSES:  
S20W POWER POLE, N&T, 131.18'  
N45E 8" X 10" GATE POST, N&T, 46.28'  
N55W 6" ELM, N&T, 41.05'  
S85E NW COR 3' X 3' STONE 33.05'

APPROVED LAND CORNER  
P.A. 215 of 1980  
Michigan County

Co. Rep. John Meyer  
Date 11/6/96



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 11-29-96