

**SURVEY & REMONUMENTATION**

DEC 16 1996

COMMISSION

GLADWIN COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 147

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 1W	E - 11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

2 DEC 96 3:33 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK ROBISON, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5			4		3		2			1	
3													
4	7	8			9		10		11			12	
5													
6	18	17			16		15		14			13	
7													
8	19	20			21		22		23			24	
9													
10	30	29			28		27		26			25	
11													
12	31	32			33		34		35			36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 GEO E. ADAIR SET POST WIT.-(1)W. PINE 10 CORNER (2)ASPEN 11 S35 1/2E 29	NO MATERIAL FOR CORNER  1950+- EDMANDS ENG-WORKING DWG.
1908 KNOX WIT.-(3)FOUND OLD CORNER 10 LINK WEST OF CENTER OF CROSSROADS MARK W/ OLD IRON 1"	1978 SEDGMAN-L.C.R.C.#210 FOUND 1/2" BAR WIT.-(6)N35W 66.90 P.P. (7)N25E 38.57 MAIL BOX POST (8)S35W 53.15 12" TWIN TREE

1978 SEDGMAN SURVEY  
WIT.-SAME AS (6),(7)&(8)

APPROVED LAND CORNER  
P.A. 915 of 1969  
Gladwin County

Co. Rep. Mark Robison  
Date 11/6/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO CORNER FOUND. FOUND WITNESS (6), N&T. SET CORNER BY MEAS. FROM NORTH (BY PAUL LAPHAM) 2644.38 & WITNESS (6) 66.90. MEAS. EAST 2656.40, REC. BY SEDGMAN 2656.06. SET GLADWIN RE-MON BY MEASURE.

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11: CORNER COMMON TO SECTIONS 28, 29, 32 & 33  
SET 5/8" X 36" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458

WITNESSES:  
N35W POWER POLE, N&T, 66.90'  
N75E 16" OAK, N&T, 129.90'  
S45E 1 1/2" X 36" REROD 42.38'  
S50W 1/2" X 36" REROD 53.32'



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 11-29-96