

SURVEY
REMONUMENTATION

DEC 16 1996

COMMISSIONER

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 152

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 1W	G - 6
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

2 DEC 96 3:34 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER
FEB 15 1997
Gladwin County

Co. Rep. [Signature]
Date 11/6/96

- A. Description of original monument and accessories and/or subsequent restoration:
- 1956 GEO E ADAIR
SET NEW POST
WIT.-(1)W. PINE 11 N45E 8
(2)W. PINE 20 S66W 9
 - 1968 PAUL LAPHAM-SECTION SUBD.
FOUND IRON & STONE
WIT.-(3)R/R TIE FE POST S 80W 32.76
(4)2" C. APPLE N50E 42.40
(5)FE COR EAST 36.20
 - 1975+- PAUL LAPHAM-PLATS
MANCHESTER REALM
FAIRFIELD REALM
 - 1981 EDMANDS ENG-ROAD PLANS
WIT.-(8)E 33 CONC MON
(7)W 33 CONC MON
(8)N24W 50.0 TO EDGE RIM M.H.
(9)E 69.94 NAIL IN FENCE POST
(10)S47E 48.76 NAIL IN U.P.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1" BAR IN C/L OF ASPHALT ROAD, FENCE AND NORTH LINE OF PLAT OF FAIRFIELD REALM TO THE EAST. FOUND (5); MEAS. 36.2 TO CENTER OF CORNER POST, BROKEN OFF AT GROUND LEVEL. FOUND (8) & (10); MEAS. AS RECORDED. FOUND NE CORNER PLAT OF MANCHESTER REALM; MEAS. 80.80, REC. 60.75. SET GLADWIN RE-MON CAP ON FOUND 1" BAR.

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6: 1/4 CORNER COMMON TO SECTIONS 15 & 18
1" IRON BAR WITH GLADWIN RE-MON CAP IN MON BOX MARKED P.S.#27458

- WITNESSES:
- S45E P.P., N&T, 48.78'
 - N24W M.H. RIM EDGE 50'
 - S88W 16" ELM, N&T, 125.45'
 - S50W 1/2" X 3/8" REROD 80.80'-RESET FROM FOUND 1/2" IRON
 - NORTH, P.K. NAIL, 2.0'
 - EAST, P.K. NAIL, 2.0'



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-29-96