

# SURVEY & REMONUMENTATION

GLADWIN COUNTY REMONUMENTATION

DEC 16 1996

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **153**

For corners in COMMISSION

<u>GLADWIN</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>20N</u> R <u>1W</u>	<u>G - 7</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

2 DEC 96 3:34 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

1856 GEO E. ADAIR  
INTERSECTED OLD COR AT POST  
WIT.-NONE

WIT.-(3)SE COR TOWNHALL N42W 88.85  
(4)SE COR WELL N50W 68.65  
(5)FENCE COR N45E 47.88

POSSIBLY 1 1/2" DEEP-SET NAIL  
WIT.-(6)NW 56.8 T.P.  
(7)NE 39.4 P.P.  
(8)SW 43.7 COR F. POST  
(9)SE 41.5 COR F. POST

1908 KNOX SURVEY  
SET GAS PIPE  
WIT.-(1)SE COR TOWNHALL NW 130 1/2  
(2)NW FENCE POST S45 1/2E 62

1973 PAUL LAPHAM SURVEY &  
WORKING DRAWING

1987 EDMANDS ENG-ROAD PLANS  
WIT.-(10)NW 86.9 TO SW COR BLDG.  
(11)NE 63.0 TO C/L M.H.  
(12)SW 128.55 TO NE COR BLDG.

1969 PAUL LAPHAM-SECTION SUBD.  
FOUND GAS PIPE

1980+/- EDMANDS ENG-REACTION

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND P.K. NAIL IN PATCH OVER 3/8" ROD 2' BELOW SURFACE IN C/L OF ASPHALT ROAD & T-ROAD TO EAST; AGREES WITH SOUTH LINE OF PLAT OF FAIRFIELD REALM. FOUND WITNESSES (11); R&M 63.0. SET GLADWIN RE-MON FROM FOUND IRON & WITNESS (11) AND PLAT OF FAIRFIELD REALM; MEAS. TO G-8, 2644.06.

SEE DOSSIER FOR DETAILED REPORT.

APPROVED LAND CORNER  
P.A. 74 of 1970  
Gladwin County


Co. Rep. Mark Robison  
Date 11/6/96

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-7: CORNER COMMON TO SECTIONS 15, 16, 21 & 22  
SET 5/8" X 36" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458 IN MONUMENT BOX.

WITNESSES:  
N45E M.H. TOP CENTER 83.05'  
N45W TWP. HALL SE COR BRICK 133.05'  
S85W BLDG (NE COR FOUNDATION) 97.90'

S30W BLDG (SE COR FOUNDATION) 156.73'  
NORTH, P.K. NAIL, 2.0'  
EAST, P.K. NAIL, 2.0'



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 11-29-96