

DEC 16 1996

COMMISSION

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 157

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 1W	G - 11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

2 DEC 96 3:35 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, MARK ROBISON, in a field survey on November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1856 GEO E. ADAIR SET POST (4)SE 48 P.P. (5)TACK IN P.P. SE 82.19 (6)TACK IN GUY POLE NE 133.54
- 1907 KNOX SURVEY FOUND CEDAR BETWEEN 2 STONES 1980 PAUL LAPHAM-WORKING DWG WIT.-NONE
- 1950 DUNDAS & EDMANDS ENG. FOUND R/R IRON WIT.-(3)NE 37.3 COR POST

APPROVED LAND CORNER
NOV 15 1996
GLADWIN COUNTY

Co. Rep. [Signature]
Date 11/2/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" X 2" REROD CAPPED, EDMANDS ENG., 0.5' BELOW SURFACE IN C/L OF INTERSECTION OF COUNTY ROADS, REMOVED AND SET GLADWIN RE-MON CAP & IRON. PAUL LAPHAM MEAS. AGREES WITH 1907 KNOX MEAS.

SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11: CORNER COMMON TO SECTIONS 27, 28, 33 & 34
SET 5/8" X 36" REROD WITH GLADWIN RE-MON CAP MARKED P.S.#27458 IN MONUMENT BOX.

- WITNESSES: N45W POWER POLE, N&T, 82.30' S80E 12" BASSWOOD, N&T, 187.80'
- S40W 6" W. PINE, N&T, 91.82' EAST, P.K. NAIL, 2.0'
- S20E CHURCH, NW COR CONC. BLOCK 135.82' NORTH, P.K. NAIL, 2.0'



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-29-96