

FEB 18 1994

GLADWIN COUNTY REMONUMENTATION PROGRAM

PAGE 13


DEC 29 '93 AM

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 20N R 1W	M-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		



GLADWIN COUNTY
REGISTER OF DEEDS
Y. Davis

Register of Deeds Stamp & File Number

I, PAUL B. LAPHAM, in a field survey on OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1837 BRINK, CEDAR 12" S 11°W, 07 LKS P. 649-650
CEDAR 8" N 54°W, 33 LKS
03-07061 H. GILBERT, 3/4" ROD IN MON. BOX
N 27°W, 72.50' - 6" TWIN MAPLE
S 73°E, 46.85' - 5" TWIN BIRCH
S 64°W, 51.60' - 4" W. BIRCH
06-30-65 HENNING, MONUMENT BOX, UNRECORDED SURVEY & REPORT
07-19-74 LAPHAM, FOUND MONUMENT BOX, LCRC #94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" x 36" BAR IN MONUMENT BOX. EXCAVATED TO 3-1/2' DEPTH - OLD ROADBED @3'.
FOUND NO ADDITIONAL EVIDENCE.
FOUND RECORDED WITNESSES:
S 73°E, 46.85' - 5" TWIN BIRCH
FD. MON. BOX & IRON, 3.7' WEST OF M-30 @
N 50°W, 45.12' - POWER POLE
N 50°E, 48.51' - POWER POLE

This Corner established in Gladwin County Remonumentation Program.
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 36" RE-ROD WITH 2" GLADWIN COUNTY MONUMENT CAP IN MONUMENT BOX.
N 50°W, 45.12' - POWER POLE
N 50°E, 48.51' - POWER POLE
S 45°E, 67.50' - 5" MAPLE
S 50°W, 44.95' - 4" STEEL GATE POST (SOUTH POST)

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by *Paul B. Lapham*
Surveyor's Michigan License No. 9433

Date 12/02/93