

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
4th day of JANUARY
 A. D. 1993 at 1:40 o'clock
P m., and recorded in
 Liber 4 of CORNERS
 on page 186
Richard J. Brown
 Register of Deeds

For corners in
Gogebic
 (County)

Located in: Corner Code #

1. Public Land Survey T 44¹/₃N R 38W C-1
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

PEER GROUP **Approved**
Richard L. Deaton 1/20/94

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary L. Pisoni, in a field survey on October 29, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on June 8, 1847.
 Original corner: Ironwood post
 Original bearing trees:

Yellow Birch	22"	N 62° E	22 links (14.52 feet)
Sugar	12"	N 31° W	34 links (22.44 feet)
Yellow Birch	20"	S 65° W	11 links (7.26 feet)
Lynn	16"	S 56° E	37 links (24.42 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found old bottom blazes on two trees facing Section corner position. No evidence found on who blazed these trees. Found old rusty U.S. Forest Service tag facing Section corner position as noted on a 874 U.S.F.S. form dated in the 1930's.

Restored corner position at record bearing and distance from the remains of the following bearing trees:

Yellow Birch	22"	N 62° E	14.52 feet (windthrown tree, large depression)
Sugar	12"	N 31° W	22.44 feet (windthrown tree, large depression)
Yellow Birch	20"	S 65° W	7.26 feet (stump hole found with yellow birch bark)

No evidence found of the Lynn bearing tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read; T44N, R38W; S-31; S-32; S-6; S-5; T43N; 1992; R.L.S. 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Sugar Maple	12"	S 34° W	25.76 feet
Sugar Maple	11"	N 08° W	18.63 feet
Sugar Maple	9"	S 56° E	22.70 feet
Steel Sign Post		North	0.66 feet

Signed by Gary L. Pisoni Date Nov 20, 1992
 Surveyor's Michigan License No. 27457

U.S.F.S. #A-5

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

