

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
3RD day of FEBRUARY
 A. D. 1993 at 10:35 o'clock
A m., and recorded in
 Liber 4 of CORNERS
 on page 220
Richard J. Brown, Jr.
 Register of Deeds

For corners in
Gogebic
 (County)

Located In: Corner Code #/

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>43N</u> R <u>38W</u> | <u>C-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat **PEER GROUP** **Approved**
 5. Private Claims _____

Richard L. Drahn 1/20/94

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gary L. Pisoni, in a field survey on November 3, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Zelotes B. Searls on August 1, 1851.

Original corner: Wood post

Original bearing trees:

Tamarack	16"	S 27°W	29 links (19.14 feet)
Spruce	10"	N 57°E	15 links (9.90 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. Found a 5" squared scribed wood post marking corner position and a rusty location poster metal tag on a 5" decayed tamarack facing corner position.

Accepted scribed wood post as being the best available evidence for restoring the corner position.

Corner is S 00°12'13"W and 2653.35 feet from the Northwest corner of Section 5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 3/4" outside diameter by 4 feet long aluminum rod monument with a 3" cast aluminum cap, stamped to read: T43N, R38W, 1/4, S-6, S-5, 1992, R.L.S. 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Tamarack	3"	N 22°W	13.03 feet
Tamarack	3"	S 40°W	3.67 feet
Black Spruce	3"	N 55°E	9.60 feet
Steel sign post		N 74°W	1.23 feet



Signed by Gary L. Pisoni Date 1/28/93
 Surveyor's Michigan License No. 27457