

Register's Office }
Gogebic County } ss.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Received for record the
3RD day of FEBRUARY

For corners in

Gogebic
(County)

Located In:

Corner Code ##

A. D. 19 93 at 10:55 o'clock
A m., and recorded in
Liber 4 of CORNERS
on page 222
Richard J. Brown, Jr.
Register of Deeds

1. Public Land Survey	T	43N	R	38W	E-2
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat **PEER GROUP** Approved
5. Private Claims _____
Richard P. Dealm 1/20/94

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Gary L. Pisoni, in a field survey on November 12, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Zelotes B. Searls on July 30, 1851.

Original corner: Wood Post

Original bearing trees:

Yellow Birch	22"	S 40° W	7 links (4.62 feet)
Hemlock	10"	N 79° E	25 links (16.50 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. Corner restored by single proportionate measurement methods on line between the Northeast Section Corner of Section 5 and the North Meander Corner between Sections 8 and 9 located on the North shore of Desolation Point.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" outside diameter by 4 feet long aluminum rod monument with a 3" cast aluminum cap, stamped to read: T43N, R38W; 1/4; S-5; S-4; 1992; R.L.S. 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Cedar	12"	N 63° W	14.36 feet
Ash	7"	N 07° W	14.34 feet
Ash	8"	N 77° E	20.67 feet
Steel Sign Post		S 43° E	0.70 feet



Signed by Gary L. Pisoni

Date 1/28/93

Surveyor's Michigan License No. 27457