

**SURVEY & REMONUMENTATION**

NOV 12 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 43N R 38W</u>	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County } SR.

Received for record the  
27<sup>TH</sup> day of OCTOBER  
A. D. 1997 at 11:15 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 248  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Sec. 15 & 16, T43N, R38W

I, Gary L. Pisoni, in a field survey on June 26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16	●	15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Zelotes B. Searls, U.S. Deputy Surveyor on July 30, 1851.

Original corner: Wood post

Original bearing trees:

Ironwood	4"	N 80°W	26 links (17.16 feet)
Sugar	12"	S 62°E	13 links (8.58 feet)

PEER GROUP APPROVED

Richard P. Drahm 10/10/97  
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found.

Set corner by single proportionate measurement methods and on line between the Northeast corner of Section 16 and the Closing corner between Sections 15 and 16 on the Michigan/Wisconsin State boundary line.

Corner Record Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: County Remonumentation, T43N, R38W, 1/4., S-16, S-15, 1997, RLS-27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Sugar Maple	11"	N 30°E	51.51 feet
Sugar Maple	14"	S 88°E	24.51 feet
Basswood	17"	S 01°W	22.08 feet
Sugar Maple	16"	N 74°W	53.89 feet
Steel sign post		N 15°W	0.67 feet



97-02

Signed by Gary L. Pisoni

Date 7-15-97

Surveyor's Michigan License No. 27457