

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gegebic County } ss.

For corners in

_____	Gogebic	Located In:	Corner Code #
_____	(County)		
1. Public Land Survey	T 43N R 39W	I-1	
	T 44N R 39W	I-13	
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Received for record the
4TH day of NOVEMBER
A. D. 1998 at 3:20 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 73
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sec. 34 and 35, T44N, R39W
Section Corner Sec. 3 and 2, T43N, R39W

I, Gary L. Pisoni, in a field survey on October 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor in 1847.
Original Corner: White Birch Post
Original Bearing Trees:
Tamarack 9" N 09° E 24 lks (15.84 feet)
Tamarack 5" N 67° W 16 lks (10.56 feet)
In 1851, Wells Burt, U.S. Deputy Surveyor, established two new bearing trees:
White Birch 10" S 35° W 12 lks (7.92 feet)
White Birch 9" S 71° E 37 lks (24.42 feet)

On 5/26/61, Donald D. Lappala RLS with the U.S. Forest Service restored the corner position from a found 1 1/4" x 36" iron pipe at record bearing and distance from the two original bearing trees and set a 2" diameter by 5' long galvanized iron pipe 18" above ground surface with a 3" diameter brass tablet stamped as follows: T44N, R39W, S-34, S-35, S-3, S-2, T43N, 1961, RLS 12585, from which he established the following blazed and scribed bearing trees:

1961 Bearing Trees:
Red Maple 6" N 04° E 9.2 feet
Red Maple 7" S 61° E 23.9 feet
White Pine 30" S 32° W 54.7 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.'s found
On 10/16/98, found the monument as described above and the following bearing objects: (All measurement taken to a nail in side of tree)

Red Maple 10" N 06° E 9.20 feet
Balsam 8" S 71° W 12.96 feet
Wood Sign post 4"x4" N 06° E 6.2 feet

Corner record research on file with County Representative.

PEER GROUP APPROVED
Richard L. Drain 10/29/98
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Oak 8" N 88° E 42.12 feet
Red Maple 8" S 35° E 8.70 feet
Steel sign post N 55° W 0.85 feet

98-G4
Signed by Gary L. Pisoni Date October 24, 1998

Surveyor's Michigan License No. 27457

