

SUPPLEMENTAL
RECORDATION

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County

For corners in

<u>Gogebic</u>		Located In:	Corner Code #
(County)			
1. Public Land Survey		<u>T 43N R 39W</u>	<u>J-1</u>
		<u>T 44N R 39W</u>	<u>J-13</u>
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Received for record the
4TH day of NOVEMBER
NOVEMBER
 A. D. 1998 at 3:20 o'clock
P m., and recorded in
 Liber 7 of CORNERS
 on page 74
Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner between Section 35, T44N, R39W and
 Section 2, T43N, R39W

I, Gary L. Pisoni, in a field survey on October 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5				4		3		2	1
3													
4		7		8				9		10		11	12
5													
6		18		17				16		15		14	13
7													
8		19		20				21		22		23	24
9													
10		30		29				28		27		26	25
11													
12		31		32				33		34		35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor in 1847.

Original Corner: Sugar Post
 Original Bearing Trees:

B. Oak	5"	N 37° E	28 lks (18.48 feet)
Sugar	16"	N 52° W	52 lks (34.32 feet)

On 5/26/61, Donald D. Lappala RLS with the U.S. Forest Service restored the corner position from the stump holes of the original bearing trees and set a 2" diameter x 5' long galvanized iron pipe 12" above ground surface with a 3" diameter brass tablet stamped as follows: T44N, R39W, 1/4, S-35, S-2, T43N, 1961 from which he established the following blazed and scribed bearing trees:

1961 Bearing Trees:

Black Oak	14"	N 72° W	53.5 feet
Black Oak	7"	N 42° E	34.3 feet
Black Oak	9"	S 17° E	38.7 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.'s found

On 10/16/98, found the monument as described above and the following bearing objects: (All measurements taken to nail in side of tree)

Black Oak	16"	N 75° W	53.51 feet
Black Oak	11"	N 40° E	34.05 feet
Black Oak	12"	S 19° E	38.75 feet
Steel sign post		N 49° E	4.0 feet

PEER GROUP APPROVED
Richard L. Drain 10/27/98
 COUNTY REGISTER

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing tree: (All measurements taken to a nail in side of tree)

Sugar Maple	10"	S 81° W	25.42 feet
-------------	-----	---------	------------

98-G3
 Signed by Gary L. Pisoni Date October 24, 1998

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN. 28, 1971

