

SURVEY & RE-MONUMENTATION

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

For corners in

Gogebic Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 43N R 39W L-1
T 44N R 39W L-13
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Received for record the
4th day of NOVEMBER
A. D. 1998 at 3:20 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 76
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner between Section 36, T44N, R39W and
Section 1, T43N, R39W

I, Gary L. Pisoni, in a field survey on October 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|---|----|---|---|----|---|----|---|---|----|----|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | | 4 | | 3 | | | 2 | 1 |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | | 9 | | 10 | | | 11 | 12 |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | | 17 | | | 16 | | 15 | | | 14 | 13 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | | 21 | | 22 | | | 23 | 24 |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | | 28 | | 27 | | | 26 | 25 |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | | 33 | | 34 | | | 35 | 36 |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor on July 2, 1847

Original Corner: Yellow Pine Post

Original Bearing Trees:

| | | | |
|-------------|----|-----|---------------------|
| Spruce Pine | 6" | N-E | 37 lks (24.42 feet) |
| Aspen | 5" | N-W | 23 lks (15.18 feet) |

On 9/21/87, I restored the corner position from a found 1" dia. iron shaft and set a 2" diameter by 30" aluminum pipe monument, flush with ground surface, over the top of the iron shaft with a 3" aluminum cap stamped as follows: T44N, R39W; 1/4; S-36; S-1; T43N, 1987; RLS 27457; from which I established the following blazed and scribed bearing trees;

| | | | | |
|---------------------|-----------------|----|---------|------------|
| 1987 Bearing Trees: | Sugar Maple | 7" | S 28° W | 23.58 feet |
| | Balsam | 6" | S 87° W | 37.08 feet |
| | Balsam | 4" | N 56° W | 29.86 feet |
| | Steel sign post | 6' | North | 1.19 feet |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.'s found.

On 10/16/98, found the monument as described above and the following bearing objects: (All measurements taken to a nail in side of tree)

| | | | |
|-----------------|----|---------|------------|
| Balsam | 4" | N 56° W | 30.02 feet |
| Steel sign post | 6' | North | 1.19 feet |

Corner record research on file with County Representative.

Richard L. Dean 10/27/98
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

| | | | |
|--------|-----|---------|------------|
| Balsam | 9" | N 60° E | 40.20 feet |
| Maple | 12" | N 83° W | 31.01 feet |

98-G1
Signed by Gary L. Pisoni Date October 24, 1998
Surveyor's Michigan License No. 27457

