

SURVEY & REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
17th day of MARCH
A. D. 1998 at 9:55 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 327
Ramona Collins Deputy
Register of Deeds

For corners in SECTION

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>39W</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>44N</u> R <u>38W</u>	<u>A-12</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 36 & 31; T.44 N., R.38-39 W.

I, Richard L. Drahn in a field survey on December 9, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 7/2/1851⁴⁷. Original B.T.s --- Aspen 7" S.31 E. 21 links (13.86') --- B. Oak 8" N.60 W. 23 links (15.18') ---

Corner re-established by Gary Pisoni (27457) on 6/8/87 using single proportionate methods. He set a 2" X 30" alum. pipe with a 3 $\frac{1}{4}$ " stamped aluminum cap and the following B.T.s:

7"	Hemlock	N.23 E.	47.14'
5"	Sugar Maple	S.37 E.	30.18'
4"	Sugar Maple	N.77 W.	27.32'
6'	Metal sign post	S.50 W.	1.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 3, Page 243 on 8/24/88.

Corner research on file with Gogebic County records.

Recovered Pisonis' monument as described and his B.T.s as follows.

8"	Hemlock	N.22 E.	47.18'
7"	Sugar Maple	S.38 E.	30.18'
4"	Sugar Maple	N.78 W.	27.32'
6'	Steel sign rail	S.41 W.	0.93'

No evidence of the GLO B.T.s recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

9" Red Pine N.16 W. 30.98'

PEER GROUP APPROVED
Richard L. Drahn 12/19/97
COUNTY REGISTER



Signed by Richard L. Drahn Date December 12, 1997

Surveyor's Michigan License No. 21564