

**SURVEY &  
REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 44N R 39W	B-9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County } ss.

Received for record the  
17<sup>th</sup> day of MARCH  
A. D. 1998 at 9:50 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 313.  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 19 & 30; T.44 N., R.39 W.

I, Richard L. Drahn in a field survey on December 7, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9	●												
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wells Burt on 8/27/1851. Original B.T.s --- Hemlock 16" S.65 W. 16 links (10.56') --- Hemlock 18" N.49 E. 34 links (22.44') ---

Corner restored by Donald D. Lappala (12585) on 7/5/72 from the remains of the two original B.T.s and natural feature ties. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s:

5"	Cedar	N.70 W.	34.4'
8"	Sugar Maple	S.17 E.	35.6'
7"	Sugar Maple	S.67 W.	58.9'
	Metal sign post	N.86 W.	2.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County USFS Liber, Page R-3 on 12/9/74

Corner research on file with Gogebic County records.

Recovered Lappalas' monument as described and his B.T.s as follows:

7"	Cedar	N.68 W.	34.42'
11"	Sugar Maple	S.16 E.	35.57'
9"	Sugar Maple	S.65 W.	58.83'
7'	Steel sign rail	N.83 W.	2.73'


Portions of both original B.T. stumps still remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New Bearing tree referenced:

9" Red Maple N.84 E. 37.42'

FIELD GROUP APPROVED  
Richard L. Drahn 12/19/97  
COUNTY REGISTER



Signed by Richard L. Drahn Date December 12, 1997

Surveyor's Michigan License No. 21564